

Millennium Science & Engineering, Inc.

1605 N. 13th Street Boise, Idaho 83702 Phone: 208.345.8292 Fax: 208.344.8007

July 17, 2007

Ms. Cheryl Robinson Air Quality Permitting Engineer Idaho Department of Environmental Quality 1410 N. Hilton Boise, Idaho 83706

RECEIVED

JUL 16 2007

DEPARTMENT OF ENVIRONMENTAL QUALITY
STATE A Q PROGRAM

RE:

Permit to Construct Application, Concrete Batch Plant, Romero General Construction, Mountain Home, Idaho

Dear Cheryl:

Please find enclosed one copy of the Permit to Construct Application for the Romero General Construction Corporation concrete batch plant in Mountain Home, Idaho. A check to pay the Permit to Construct application fees is also enclosed.

Thank you for your assistance with this project. If you have any questions please call me at (208) 345-8292.

Regards,

Troy D. Riécke, P.E. Environmental Engineer

Cc: Mr. Dale Pettibone – Romero General Construction Corp.



IDAHO DEPARTMENT OF **ENVIRONMENTAL QUALITY**

1410 North Hilton Boise, Idaho 83706-1253

		RE	CEIPI	07-1	18-07
RECEIVED FRO	M Rom.	ero G	2 2N2\$21		DATE
			n die		
SOURCE Cash	Check -	Money	Order 🗌 No	2200	846
DESCRIPTION	I grant	: :			UNT OF PAYMEN
PTC	Apple	cotron	700	/	000 00
		*			1/
·	· · · · · · · · · · · · · · · · · · ·				
	, ,				
	***************************************			1	
RECEIVED BY			TOTAL		<u> </u>
	ye		TOTAL RECEIVED	//0	20.00
PID	OBS	CA	SUB-OBJ	WP	BE

№ 82767

JUL 16 2007

DEPARTMENT OF ENVIRONMENTAL QUALITY STATE A Q PROGRAM

Permit to Construct Application

Romero General Construction Corp. **Concrete Batch Plant** Mountain Home, Idaho

July 17, 2007

Prepared for:



2150 N. Centre Pkwy, Suite I Escondido, CA 92026

Prepared by:

Millennium Science & Engineering, Inc. 1605 North 13th Street Boise, Idaho 83702 (208)345-8292

Millennium Science & Engineering, Inc. Environmental Science & Engineering Solutions for the 21st Century



LIST OF ATTACHMENTS

Attachment 1 – Permit Application Forms

Attachment 2 - Ambient Impact Assessment

Attachment 3 - Emission Estimates

Attachment 4 - Equipment Specifications

Attachment 5 – Air Modeling Input/Output Files

R1885.doc



Attachment 1

Permit Application Forms



DEQ AIR QUALITY PROGRAM 1410 N. Hilton, Boise, ID 83706 For assistance, call the Air Permit Hotline – 1-877-5PERMIT

PERMIT TO CONSTRUCT APPLICATION

Revision 3 04/03/07

Please see instructions on page 2 before filling out the form.

C	OMPAN	Y NAME, FACILITY NAME, AND FACILITY ID NUMBE	ER			
1. Company Name		Romero General Construction				
2. Facility	Name	MT Home AFB 3. Facility ID No.				
Brief Price One senter	oject Descri	ption - Relocate and operate concrete batch plant from Washington	n location			
		PERMIT APPLICATION TYPE				
5. 🛚 Nev	/ Facility	New Source at Existing Facility Unpermitted Existing So	ource			
		Source: Permit No.: Date Issued:				
		forcement Action: Case No.:				
6. 🗵 Min	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Major PTC				
34 7 : 2		FORMS INCLUDED				
Included	N/A	Forms	DEQ Verify			
\boxtimes		Form GI – Facility Information				
		Form EU0 – Emissions Units General				
		Form EU1 - Industrial Engine Information Please Specify number of forms attached:				
		Form EU2 - Nonmetallic Mineral Processing Plants Please Specify number of forms attached:				
		Form EU3 - Spray Paint Booth Information Please Specify number of forms attached:				
		Form EU4 - Cooling Tower Information Please Specify number of forms attached:				
		Form EU5 – Boiler Information Please Specify number of forms attached:				
		Form HMAP – Hot Mix Asphalt Plant Please Specify number of forms attached:				
\boxtimes		Form CBP - Concrete Batch Plant Please Specify number of forms attached:				
		Form BCE - Baghouses Control Equipment				
		Form SCE - Scrubbers Control Equipment				
\boxtimes		Forms EI-CP1 - EI-CP4 - Emissions Inventory– criteria pollutants (Excel workbook, all 4 worksheets)				
\boxtimes		PP Plot Plan				
\boxtimes		Forms MI1 – MI4 – Modeling Excel workbook, all 4 worksheets)				
\boxtimes		Form FRA – Federal Regulation Applicability				

DEQ USE ONLY
Date Received
Project Number
Payment / Fees Included?
Yes 🗌 No 🗌
Check Number



PERMIT TO CONSTRUCT APPLICATION

Revision 3 03/26/07

Please see instructions on page 2 before filling out the form.

All information is required. If information is missing, the application will not be processed.

	IDENTIFICATION					
1. Company Name	Romero General Construction Corp.					
2. Facility Name (if different than #1)	Mountain Home Idaho					
3. Facility I.D. No.						
4. Brief Project Description:	Concrete batch plant					
	FACILITY INFORMATION					
5. Owned/operated by: (√if applicable)	Federal government County government State government City government					
Primary Facility Permit Contact Person/Title	Dale Pettibone, Superintendent					
7. Telephone Number and Email Address	760-489-8412 (office) 208-413-5056 (cell) dpettibone@romerogc.com					
8. Alternate Facility Contact Person/Title						
9. Telephone Number and Email Address						
10. Address to which permit should be sent	4525 NE Lott Road					
11. City/State/Zip	Mountain Home, ID 83647					
12. Equipment Location Address (if different than #10)	Mountain Home Air Force Base UTM: 11T 590869m E 4768127m N					
13. City/State/Zip	Mountain Home, Idaho					
14. Is the Equipment Portable?	Yes No					
15. SIC Code(s) and NAISC Code	Primary SIC: 3531 Secondary SIC (if any): NAICS: 327320					
16. Brief Business Description and Principal Product	Concrete batch plant					
17. Identify any adjacent or contiguous facility that this company owns and/or operates						
	PERMIT APPLICATION TYPE					
18. Specify Reason for Application	 ☑ New Facility ☐ Modify Existing Source: ☐ Permit Revision ☐ Required by Enforcement Action: ☐ Case No.: 					
	CERTIFICATION					
	ILES FOR THE C ONTROL OF A IR P OLLUTION IN I DAHO), I CERTIFY BASED ON INFORMATION AND BELIEF FORME HE STATEMENTS AND INFORMATION IN THE DOCUMENT ARE TRUE, ACCURATE, AND COMPLETE.	:D				
19. Responsible Official's Name/Title	See signature on CBP form					
20. RESPONSIBLE OFFICIAL SIGNATU	RE Date:					
21. Check here to indicate you would	ike to review a draft permit prior to final issuance.					



PERMIT TO CONSTRUCT APPLICATION

Revision 4 04/18/07

Please see instructions on page 5 before filling out the form.

GENERAL INFORMATION

Company Name:	Romero General Construction	an algeria e e espera esta de la estigación de la estagación de la estagación de la estagación de la estagación			
Facility Name:	Mountain Home Air Force Base Facility ID No:				
Brief Project	Locate and operate concrete batch plant				
Description:	Locate and operate concrete batter plant		•		
Mailing Address:	4525 NE Lott Road				
City:	Mountain Home	State:	ID .		
Zip Code:	83647	County:	Elmore		
General Nature of					
Business & Products:	Asphalt concrete placing	artegoria con contrata (Albara)			
		· · · · · · · · · · · · · · · · · · ·			
Contact Name, Title:	Dale Pettibone, Superintendent				
Phone:	760-489-8412	Cell:	208-413-5056		
Email:	dpettibone@romerogc.com				
Owner or Responsible					
Official Name, Title:	Dale Pettibone, Superintendent				
Phone:	208-413-5056				
Email:	dpettibone@romerogc.com				
Proposed Initial Plant Location:	Mountain Home Air Force Base				
Nearest City:	Mountain Home				
County:	Elmore	Estimated Startup Da			
oounty.					
Reason for Application:	Permit to construct a new source Permit to operate an existing unpermitted so Permit to modify/revise an existing permitted Permit No.: Issue Date: Facility ID:		ntify the permit below)		
□ Check here to indicate	te you would like to review a draft permit prior to fi	nal issuance			
	6 month operation, existing equipment to be mov to accept separation distance between crusher a state in permit.				

CONCRETE BATCH PLANT INFORMATION

1. Concrete Batch Plant

Manufacturer:	CON-E-CO		Model:	Lo-Pro 12 Concrete Batch Plant
Manufacture Date:	05-05			
Maximum Hourly Thre	oughput:	120 (cy/hour)		
Maximum Daily Throughput:		2880 (cy/day)		
Maximum Annual Throughput:		1,051,200 (cy/year)		
Requested Annual Th	roughput:	1,051,200 (cy/year)		

2a. Cement Storage Silo Baghouse No. 2

Manufacturer: CON-	E-CO	Model: PJC-300S				
Stack Height from Ground:	47.5 (ft)	Exit Air Flow Rate: 1,500 (acfm)				
Stack Inside Diameter:	downward discharge (ft)	* PM ₁₀ Control Efficiency: 99 (%)				
* Manufacturer Grain Loadin	ng Guarantee:					
* Attach manufacturer's PM ₁₀	* Attach manufacturer's PM ₁₀ control efficiency if available.					

2b. Cement Storage Silo Baghouse No.

Manufacturer:		Model:				
Stack Height from Ground:	(ft)	Exit Air Flow Rate:	(acfm)			
Stack Inside Diameter:	(ft)	* PM ₁₀ Control Efficiency:	(%)			
* Manufacturer Grain Loading Guarantee:						
* Attach manufacturer's PM ₁₀ control efficiency if available.						

2c. Cement Supplement (such as flyash) Storage Silo Baghouse No. 1

Manufacturer:	CON-I	I-E-CO		Model: PJC-300S		
Stack Height from	Ground:	20.9 (ft)		Exit Air Flow Rate:	1,000 (acfm)	
Stack Inside Diameter: downward discharge		charge (ft)	* PM ₁₀ Control Efficiency:	99 (%)		
* Manufacturer Grain Loading Guarantee:						
* Attach manufactur	* Attach manufacturer's PM ₁₀ control efficiency if available.					

2d. Cement Supplement (such as flyash) Storage Silo Baghouse No. _____

Manufacturer:		Model:				
Stack Height from Ground:	(ft)	Exit Air Flow Rate:	(acfm)			
Stack Inside Diameter:	(ft)	* PM ₁₀ Control Efficiency:	(%)			
* Manufacturer Grain Loading Guarantee:						
* Attach manufacturer's PM ₁₀ co	ontrol efficiency if available	e.				

3. Weigh Batcher Baghouse(s)

Manufacturer:	CON-	E-CO		Model: 14-23		
Stack Height from G	round:	18.3 (ft)		Exit Air Flow Rate:	180 (acfm)	
Stack Inside Diameter: Downward discharge (ft)		* PM ₁₀ Control Efficiency:	99 (%)			
* Manufacturer Grain Loading Guarantee:					·	
* Attach manufacturer	* Attach manufacturer's PM ₁₀ control efficiency if available.					

ELECTRICAL GENERATOR SET INFORMATION (if applicable)

Manufacturer:	MQ Power		ı	Model: DCA180SSJ			
Maximum Rated Capacit	y:	315	⊠ Hp	☐ kW			
Fuel Type:		☐ Gasoline	□ Diesel	☐ Natural Gas ☐ Propane			
Maximum Fuel Usage Ra	ate:	11.4	⊠ gal./hr.	☐ cfh			
Maximum Daily Hrs. of C	perations:	24 (hours/day	')				
Maximum Annual Hrs. of	f Operations:	8760 (hours/y	ear)				
Stack Parameters:	Stack Height f	rom Ground (ft):	<u>5</u>	Stack Exhaust Flow Rate (acfm): 1371			
	Stack Insi	de Diameter (ft):	<u>.38</u>	Stack Exhaust Gas Temperature (°F): 800			
ADDITIONAL GENERA	TOR (if appli	cable)					
Manufacturer:				Model:			
Maximum Rated Capacit	y:		☐ Hp	□ kW			
Fuel Type:		☐ Gasoline	☐ Diesel	I ☐ Natural Gas ☐ Propane			
Maximum Fuel Usage Ra	ate:		☐ gal./hr	r. 🔲 cfh			
Maximum Daily Hrs. of C	perations:	(hours	s/day)				
Maximum Annual Hrs. of	Operations:	(hours	s/year)				
Stack Parameters:	Stack Height f	rom Ground (ft):		Stack Exhaust Flow Rate (acfm):			
	Stack Insi	de Diameter (ft):		Stack Exhaust Gas Temperature (°F):			
⊠ \$1,000 PTC application fee enclosed							
	d on information attached and/	on and belief for or referenced o	rmed after re document(s)	onsible Official) reasonable inquiry, the statements and information reasonable accurate, and complete in accordance with July 17, 2007			
Responsible Official Signature	Superinte Responsib	endent ole Official Title					
Dale Pettibone Print or Type Responsible Office	ial Name						



DEQ AIR QUALITY PROGRAM

1410 N. Hilton, Boise, ID 83706 For assistance, call the

Air Permit Hotline - 1-877-5PERMIT

PERMIT TO CONSTRUCT APPLICATION Revision 3 4/5/2007

Please see instructions on page 2 before filling out the form.

Company Name: Romero General Construction Corp. Facility Name: Mountain Home Air Force Base Facility ID No.:

Facility ID No.:													
Brief Project Description:													
		MARY OF F	ACILITY WI	DE EMISSI	ON RATES F	OR CRITE		Charter and the Control	INT SOURC	ES	199 <i>9</i> 00 c.		
1.	2.	PN	A					3.			-		
Emissions units	Stack ID	lb/hr	T/yr	lb/hr	O ₂ T/yr	lb/hr	O _X T/yr	lb/hr	O T/yr	lb/hr	C T/yr		ad
	9179 J. Kill. 1981.	1D/H1	1791	וויינו	Point So		17yl	ID/III	1/yr	ID/NF	i/yr	lb/hr	T/yr
Cement Storage Bin 1	P1	0.08	0.37										
Cement Storage Bin 2	P2	0.08	0.37										
Cement Batcher	P3	0.05	0.21										
Electric Generator	P4	0.06	0.24	0.65	2.83	1.76	7.70	0.31	1.37	0.78	3.41		
name of the emissions unit5													
name of the emissions unit6													
name of the emissions unit7													
name of the emissions unit8													
name of the emissions unit9													
name of the emissions unit10													
name of the emissions unit11													
name of the emissions unit12													
name of the emissions unit13													
name of the emissions unit14													
name of the emissions unit15													
name of the emissions unit16													
name of the emissions unit17			research and										
name of the emissions unit18													
name of the emissions unit19													
name of the emissions unit20													_
name of the emissions unit21													
(insert more rows as needed)													
Total		0.27	1.19	0.65	2.83	1.76	7.70	0.31	1.37	0.78	3.41		



DEQ AIR QUALITY PROGRAM 1410 N. Hilton, Boise, ID 83706 For assistance, call the Air Permit Hotline - 1-877-5PERMIT

PERMIT TO CONSTRUCT APPLICATION

Revision 3 4/5/2007

Please see instructions on page 2 before filling out the form.

	riodos dos madadelarios dir paga 2 botaro immig dal dio torri.
Company Name:	Romero General Construction Corp.
Facility Name:	Mountain Home Air Force Base
Facility ID No.:	
Brief Project Description:	Concrete Batch Plant

Brief Project Description:													
		Y OF EMISS	SIONS INCR	EASE (PRC	POSED PT	E - PREVIO			- POINT SO	URCES			
1.	2.	PM	40	SC) _o	NO	ე _ა 1	C	0	VC)C	I e	ead
Emissions units	Stack ID	lb/hr	T/yr	lb/hr	T/yr	lb/hr	T/yr	lb/hr	T/yr	lb/hr	T/yr	lb/hr	T/yr
4					Point So								1
Cement Storage Bin 1	P1	0.08	0.37										
Cement Storage Bin 2	P2	0.08	0.37										
Cement Batcher	P3	0.05	0.21										
Electric Generator	P4	0.06	0.24	0.65	2.83	1.76	7.70	0.31	1.37	0.78	3.41		
name of the emissions unit5													
name of the emissions unit6													
name of the emissions unit7													
name of the emissions unit8													
name of the emissions unit9	1												
name of the emissions unit10													
name of the emissions unit11													
name of the emissions unit12													
name of the emissions unit13													
name of the emissions unit14													
name of the emissions unit15													
name of the emissions unit16													
name of the emissions unit17													
name of the emissions unit18							:						
name of the emissions unit19													
name of the emissions unit20													
name of the emissions unit21													
(insert more rows as needed)							,						
Total		0.27	1.19	0.65	2.83	1.76	7.70	0.31	1.37	0.78	3.41		



Total

DEQ AIR QUALITY PROGRAM

1.46

6.39

PERMIT TO CONSTRUCT APPLICATION

	1410 N. Hilton, Bo For assistance, ca Air Permit Hotline	II the	MIT										Revision 3 4/5/2007
ON	In	S11: O-		ease see instr	ructions on pag	e 2 before fillin	g out the form.						
Company Name: Facility Name:	Romero General C	construction Co	rp.			Mountain	Home Air Force	e Base					
Facility ID No.:													
Brief Project Description:	Concrete Batch Pl	ant			- January - January - 19	ala a sana a sana a sana		- 1,500 - 1,1		and the second training the second	di deka wasan di sasar	State of the state	, 1945 1939e
	SUMMARY	OF EMISSIO	ONS INCRE	ASE (PRO	POSED PTE	- PREVIOU		مناحث سيخشب بيب	FUGITIVE S	OURCES			
1.	2.		3. Air Pollutant Maximum Change in Emissions Rate (lbs/hr or t/yr)										
		PN	110	s	O ₂	N	O _X	С	0	V	ОС	Le	ad
Fugitive Source Name	Fugitive ID	lb/hr	T/yr	lb/hr	T/yr	lb/hr	T/yr	lb/hr	T/yr	lb/hr	T/yr	lb/hr	T/yr
			\$47		Fugitive S	ource(s)	antid. Salah sa	1					
Aggregate delivery to storage	F1	0.37	1.63										
Sand delivery to storage	F2	0.08	0.37										
Aggregate transfer to conveyor	F3	0.37	1.63										
Sand transfer to conveyor	F4	0.08	0.37										
Truck loading (truck mix)	F5	0.55	2.39										
name of fugitive source6													
name of fugitive source7													
name of fugitive source8													
name of fugitive source9													
name of fugitive source10													
name of fugitive source11													
name of fugitive source12													
name of fugitive source13													
name of fugitive source14													
name of fugitive source15													
name of fugitive source16											·		
name of fugitive source17													
name of fugitive source18													
name of fugitive source19													
name of fugitive source20													
name of fugitive source21													
(insert more rows as needed)													
		1					1	1	1			l	1





1,000

2,000

Millennium Science & Engineering, Inc.

1605 North 13th Street Boise, ID 83702 Phone: (208) 345-8292

Site Map

Romero Construction Proposed Concrete Batch Plant

Mountain Home Air Force Base Elmore County, Idaho

7-17-07

TDR

Figure 1

(Scale in Feet)

SOURCE: Google Earth, 2007.

Modeling Information - Impact Analysis Form M11



DEQ AIR QUALITY PROGRAM 1410 N. Hilton, Boise, ID 83706 For assistance, call the Air Permit Hotline - 1-877-5PERMIT

PERMIT TO CONSTRUCT APPLICATION

Revision 3 4/5/2007

Please see instructions on page 2 before filling out the form.

Company Name: Romero General Construction Corp.

Facility Name: Mountain Home Air Force Base

Facility ID No.:

Brief Project Description: Concrete Batch Plant SUMMARY OF AIR IMPACT ANALYSIS RESULTS - CRITERIA POLLUTANTS 1. 2. 5. Significant **Full Impact** Impact Significant **Background Total Ambient Analysis Averaging NAAQS** Percent of Contribution **Analysis** Criteria Pollutants Concentration Impact Period Results $(\mu g/m3)$ **NAAQS** Results Level (µg/m3) $(\mu g/m3)$ $(\mu g/m3)$ $(\mu g/m3)$ $(\mu q/m3)$ 73.00 83.59 24-hour 5 10.59 150 56% PM₁₀ 26.88 54% Annual 1 0.88 26.00 50 25 2.96 3% 3-hr 34.00 36.96 1300 SO_2 27.08 24-hr 5 1.08 26.00 365 7% 8.00 8.22 Annual 1 0.22 80 10% NO_2 Annual 1 0.59 17.00 17.59 100 18% 2.87 3,600.00 3,602.87 36% 1-hr 2000 10000 CO 2,300.00 8-hr 500 1.03 2,301.03 40000 6%



(insert more rows as needed)

DEQ AIR QUALITY PROGRAM 1410 N. Hilton, Boise, ID 83706

PERMIT TO CONSTRUCT APPLICATION

For assistance, call the 3/27/2007 Air Permit Hotline - 1-877-5PERMIT Please see instructions on page 2 before filling out the form. Company Name: Romero General Construction Corp. Facility Name: Mountain Home Air Force Base Facility ID No .: Brief Project Description: Concrete batch plant POINT SOURCE STACK PARAMETERS 1. 2. 3a. 3b. 5. 7. 8. 9. 10. Base Stack Exit Stack Exit Stack Exit Stack orientation UTM Easting UTM Stack Modeled Stack ID Elevation Temperature Flowrate Velocity (e.g., horizontal, rain (m) Northing (m) Height (m) Diameter (m) (acfm) (K) (m) (m/s) cap) **Emissions units** Point Source(s) Concrete Batch Plant Group **CBPG** 590869 4768127 911.00 2.00 0.001 ambient 0.00 0.001 grouped emission P4 590869 4768127 911.00 1.50 0.12 Eletric Generator 699.82 1,371.00 63.04 name of the emissions unit3 name of the emissions unit4 name of the emissions unit5 name of the emissions unit6 name of the emissions unit7 name of the emissions unit8 name of the emissions unit9 name of the emissions unit10 name of the emissions unit11 name of the emissions unit12 name of the emissions unit13 name of the emissions unit14 name of the emissions unit15 name of the emissions unit16 name of the emissions unit17 name of the emissions unit18 name of the emissions unit19 name of the emissions unit20 name of the emissions unit21



DEQ AIR QUALITY PROGRAM 1410 N. Hilton, Boise, ID 83706 For assistance, call the

PERMIT TO CONSTRUCT APPLICATION

Revision 3 4/5/2007

	Air Permit Hot	line - 1-877-5PE	RMIT							4/5/2007
		Please	see instructio	ns on page 2	before filling	out the form.				
	Romero Gener	al Construction C	orp.							
Facility Name:					Mountain Hor	ne Air Force Bas	e			
Facility ID No.:	Concrete Batch	Diest								
Brief Project Description:	Concrete Batch	i Plant	FUCITIVI	E SOURCE P.	ADAMETED	. 1. 1. 1. 1.	A		the company of the	2700 a sa
							<u> </u>		. " : **	
1.	2.	3a.	3b.	4.	5.	6.	7.	8.	9.	10.
Emissions units	Stack ID	UTM Easting (m)	UTM Northing (m)	Base Elevation (m)	Release Height (m)	Easterly Length (m)	Northerly Length (m)	Angle from North (°)	Initial Vertical Dimension (m)	Initial Horizontal Dimension
Area Source(s)								the state of the s	· .	(m)
Fugitive emission sources included in	n point source	group		50			<u>,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</u>	d ver		
name of the emissions unit2		<u> 9</u> . очр								
name of the emissions unit3										
name of the emissions unit4							ER PURISHBURGE CONTRACTOR			-
name of the emissions unit5										
name of the emissions unit6										
name of the emissions unit7										
name of the emissions unit8										
name of the emissions unit9										
name of the emissions unit10										
Volume Source(s)					eri L		10 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	e		
name of the emissions unit11										
name of the emissions unit12										
name of the emissions unit13										
name of the emissions unit14										
name of the emissions unit15										
name of the emissions unit16										
name of the emissions unit17										
name of the emissions unit18										
name of the emissions unit19										
(insert more rows as needed)									!	



DEC AIR QUALITY PROGRAM

PERMITTO CONSTRUCT APPLICATIONS

	DEQ AIR QU 1410 N. Hilto For assistand Air Permit H	on, Boise, ID ce, call the	83706			PERMIT TO CONSTRUCT APPLICATION Revision 3 4/5/2007					
				s on page 2 l	before filling out th	e form.					
Company Name:	Romero Gen	eral Constru	ction Corp.								
Facility Name:					Mountain Home Air F	orce Base					
Facility ID No.:											
Brief Project Description:	Concrete Ba				and the second s						
		BUILDING AND STRUCTURE INFORMATION									
1.	2.	3.	4.	5.	6.	7.					
Building ID Number	Length (ft)	Width (ft)	Base Elevation (m)	Building Height (m)	Number of Tiers	Description/Comments					
Building 1 ID						No Building Downwash Considered					
Building 2 ID											
Building 3 ID											
					Saturation () (
(insert more rows as needed)											
· · · · · · · · · · · · · · · · · · ·											
	<u> </u>		l								



PERMIT TO CONSTRUCT APPLICATION

Revision 3 03/26/07

Please see instructions on page 2 before filling out the form.

	DENTIFICATIO	N					
Company Name:	Facility Name:			Facility ID No:			
Romero General Construction Corp.	Mountain Home Air Force Base						
Brief Project Description: Concrete Batch Pla	nt						
APPLIC	ABILITY DETE	RMINATION					
1. Will this project be subject to 1990 CAA Section 112(g)?		⊠ NO	☐ YES	**			
(Case-by-Case MACT)			it must submit an applic mination [IAC 567 22-1				
Will this project be subject to a New Source Performance Stance (40 CFR part 60)	lard?	.⊠ NO	☐ YES	*			
(40 GIN part 60)		*If YES, please id	lentify sub-part:	-			
3. Will this project be subject to a MACT (Maximum Achievable Coregulation? (40 CFR part 63)	_	☑ NO *If YES, please id	☐ YES	*			
THIS ONLY APPLIES IF THE PROJECT EMITS A HAZARDOUS AIR POLLUT	ANT						
4. Will this project be subject to a NESHAP (National Emission Statement Hazardous Air Pollutants) regulation?	andards for	⊠ NO	☐ YES	*			
(40 CFR part 61)		*If YES, please id	lentify sub-part:	-			
5. Will this project be subject to PSD (Prevention of Significant De (40 CFR section 52.21)	terioration)?	⊠ NO	☐ YES				
6. Was netting done for this project to avoid PSD?		⊠ NO	☐ YES	*			
o. Tras nothing done for this project to avoid F3D?		*If YES, please at	ttach netting calculation	S			
IF YOU ARE UNSURE HOW TO ANSWER ANY	OF THESE QUE:	-	THE AIR PERMIT H	OTLINE AT			



Attachment 2

Ambient Impact Assessment



AMBIENT IMPACT ASSESSMENT

Introduction

Romero General Construction Corporation (Romero) proposes to move a portable concrete batch plant currently located in Washington state to a location at the Mountain Home Air Force Base southwest of Mountain Home, Idaho (see Site Map). This batch plant will be a temporary installation that is only expected to be in operation for up to six months. Millennium Science & Engineering, Inc (MSE) was contracted by Romero to complete an ambient impact assessment to support their Permit to Construct (PTC) application for the concrete batch plant.

Air dispersion modeling was performed by MSE to demonstrate compliance with NAAQS for criteria pollutants and Idaho Department of Environmental Quality (IDEQ) screening levels for TAPs in support of a PTC Application for the Romero concrete batch plant. Due to time constraints, a modeling protocol was not prepared. The IDEQ provided modeling guidance for this project in an e-mail dated July 12, 2007.

Model Description / Justification

Air dispersion modeling was performed using the Environmental Protection Agency (EPA) AERMOD model. Due to relatively low estimated emission concentrations and the significant separation distance between the source and the nearest property boundary modeling was simplified as follows:

- 1.) The concrete batch plant emissions from each process were summed together and modeled as a single point.
- 2.) The electric generator emissions were modeled at the same location as the concrete batch plant.
- 3.) Separate modeling runs were completed for the concrete batch plant and the electric generator. A unit emission factor of 1 gram per second (g/s) was utilized to allow the same model run to be used for each of the potential pollutants of concern.
- 4.) Since the nearest property fenceline (ambient impact boundary) will be 955 meters from the source MSE established receptors using a polar grid with a radius of 955 meters.
- 5.) Because of the significant separation distance between the source and ambient impact boundary and uncertainties associated with the exact plant layout MSE assumed no building downwash. MSE performed one modeling run with a square building with sides 10 meters in length and 5 meters tall. The presence of this building had no impact on the predicted ambient air concentrations at the nearest ambient impact boundary; therefore, further modeling did not include any consideration for building downwash.

Emission and Source Data

Emissions from the concrete batch plant consist of three point sources (Cement Storage Bin 1, Cement Storage Bin 2, and Cement Batcher) and five fugitive

Romero General Construction - Concrete Batch Plant

Mountain Home, Idaho



emission sources (aggregate delivery to ground storage, sand delivery to ground storage, aggregate transfer to conveyor, sand transfer to conveyor, and truck loading). To simplify modeling all of these emission sources were represented as a single point source (Concrete Batch Plant Group). Emissions from each source within the Concrete Batch Plant Group were calculated using EPA AP-42 emission factors and vendor supplied information. Four pollutants were considered for modeling from the Concrete Batch Plant Group: PM10, arsenic, chromium (VI), and nickel.

The electric generator emissions were modeled at the same location as the Concrete Batch Plant Group for modeling simplification. The emission rates for the generator were estimated from AP-42 emission factors and vendor supplied information. Four pollutants were considered for modeling from the generator: PM10, NOx, SOx, and CO.

Attachment 3 summarizes the emission estimates completed for this project and Attachment 4 provides equipment specifications. Table 1 summarizes the emission source characteristics used in the ambient impact analysis. All modeling was performed using the maximum potential to emit.

Receptor Network

A receptor network was established so that ambient concentrations could be evaluated. The first step in this process was to determine the location of the ambient air boundary and the second step was to assign receptor locations within the ambient air zone.

Ambient Air Boundary

The ambient air boundary was established as the facility's fenceline (see Site Map, for location of the fenceline). The proposed facility will be located at an active military base. The site is secure and actively monitored by security personnel to prevent unauthorized entry.

Receptors

To streamline modeling, receptors were established only at a simplified worse-case Ambient Air Boundary. This simplified Ambient Air Boundary was established as a circle with a radius equal to the shortest distance from the proposed source to the fenceline (955 meters). The maximum ambient impact was determined to occur at the facility's fenceline; therefore, receptors were only established along the Ambient Air Boundary.

Elevation Data

The site is relatively flat with very little variation in elevation (maximum of 10 feet). Because there is very little elevation change across the site, MSE assumed flat terrain for modeling purposes



Table 1 **Emission Source Characteristics**

	·	T	_		Jource o							
					_			Emissi	on Rates	(g/s) ³		
Emission Source	Unit ID	Stack Height (m)	Stack Diam. (m)	Exhaust Temp. (°F)	Stack Gas Vel. (m/s)	PM ₁₀	NOx	СО	SOx	As	Cr (VI)	Ni
Cement Storage Bin 1	P1	6.4	cover	ambient	cover	0.0106				3.7E-6	1.4E-6	8.5E-6
Cement Storage Bin 2	P2	14.5	cover	ambient	cover	0.0106				2.3E-9	3.2E-9	2.3E-8
Cement Batcher	P3	5.6	cover	ambient	cover	0.006						
Aggregate delivery to ground Storage	F1	fugitive	fugitive	ambient	fugitive	0.0469						
Sand delivery to ground storage	F2	fugitive	fugitive	ambient	fugitive	0.0106						
Aggregate transfer to conveyor	F3	fugitive	fugitive	ambient	fugitive	0.0469						
Sand transfer to conveyor	F4	fugitive	fugitive	ambient	fugitive	0.0106						
Truck loading	F5	fugitive	fugitive	ambient	fugitive	0.0688				5.0E-6	3.5E-6	2.0E-5
Concrete Batch Plant Group 1,2	CBPG	2	0.001	ambient	0.001	0.211	-			8.7E-6	4.9E-6	2.9E-5
Electric Generator ²	P4	1.5	0.12	800	63.04	0.007	0.221	0.039	0.081			

Notes:

- (1) Stack gas velocity set to 0.001 m/s and diameter set to 0.001 m for modeling purposes since a cover over each baghouse causes downward flow.
- (2) Modeling was performed for two sources, the Concrete Batch Plant Group and the Electric Generator. The Concrete Batch Plant Group includes three point sources and five fugitive emission sources.
- (3) Modeling was performed utilizing a generic unit emission rate of 1 g/s. Model results for individual pollutants of concern were calculated by multiplying model determined ambient air concentrations by the pollutant emission rates.



Meteorological Data

Preprocessed meteorological data (surface and upper air) from the Boise airport was provided by the IDEQ. This data was processed by IDEQ using AERMET; the output files provided by the IDEQ were used as inputs to the AERMOD model for this site.

Land Use Classification

The land use around the proposed source is an United States Air Force Base. The Air dispersion modeling was performed using a "rural" classification.

Background Concentrations

Table 2 summarizes the criteria pollutant background concentrations. Criteria pollutant background concentrations for small town/suburban areas were provided by Kevin Schilling of the IDEQ.

Evaluation of Compliance With Standards

To determine compliance with NAAQS, the applicable background concentrations were added to maximum predicted ambient concentrations determined from air dispersion modeling to result in total ambient concentrations. These total ambient air concentrations were compared to the NAAQS. Table 2 summarizes the air dispersion modeling results and compares the total predicted ambient air concentration to the applicable NAAQS. Based on this evaluation, no NAAQS are predicted to be exceeded by emissions from the sources, if operated and configured as proposed in this application. See Attachment 5 for detailed modeling output summary and electronic modeling input/output files.

Table 2
Results of Ambient Impact Assessment for Criteria Pollutants

(All Concentrations in Units of µg/m³)

	Averaging	Maximum Air Dispersion	Co	ompliance De	monstratio	1
Pollutant	Period	Model Output	Background	Total	NAAQS	% NAAQS
PM10	24 hr, 2 nd high	11	73	84	150	56%
	Annual	0.88	26	27	50	54%
NOx	Annual	0.59	17	18	100	18%
SOx	3 hr, 2 nd high	3.0	34	37	1300	2.8%
	24 hr, 2 nd high	1.1	26	27	365	7.4%
	Annual	0.22	8	8	80	10%
СО	1hr, 2 nd high	2.9	3,600	3,603	40,000	9%
	8hr, 2 nd high	1.0	2,300	2,301	10,000	23%

Evaluation of Ambient Impact Assessment for TAPs

Table 3 summarizes the results of air dispersion modeling performed to evaluate the ambient impact for TAPs. None of the AACC were exceeded by any of the maximum



predicted ambient air concentrations; therefore, the predicted ambient impact from TAP emissions is acceptable.


Table 3

Results of Ambient Impact Assessment for Toxic Air Pollutants


(All Concentrations in Units of ug/m³)

	(All Concentrations in Units of µg/III)											
Pollutant	Averaging Period	Maximum Air Dispersion Model Output	Idaho AACC	% of AACC								
Arsenic	Annual, 1 st high	3.54E-5	2.3E-4	15.4%								
Chromium (VI)	Annual, 1 st high	1.99E-5	8.3E-5	24.0%								
Nickel	Annual, 1 st high	1.18E-4	4.2E-3	2.8%								





SOURCE: Google Earth, 2007.





Attachment 3

Emission Estimates

Particulate Matter Emission Calculations

Temporary Concrete Batch Plant, Mountain Home, Idaho Romero General Construction Corp.

		PM Emission Factor	PM Emission Rate		PM Emiss	ion Rate
		Uncontrolled	Uncontrolled	Control	Contro	olled
Source	Controls	(lb/yd ³ concrete)	(lb/hr)	Efficiency	(lb/hr)	(ton/yr)
Cement Storage 1 Bin	PJC-300S	0.07	8.4	99.0%	0.084	0.37
Cement Storage 2 Bin	PJC-300S	0.07	8.4	99.0%	0.084	0.37
Cement Batcher (weigh hopper?)	BV-14 D	0.04	4.8	99.0%	0.048	0.21
Aggregate delivery to ground storage		0.0031	0.372	0.0%	0.372	1.63
Sand delivery to ground storage		0.0007	0.084	0.0%	0.084	0.37
Aggregate transfer to conveyor		0.0031	0.372	0.0%	0.372	1.63
Sand transfer to conveyor		0.0007	0.084	0.0%	0.084	0.37
Truck loading (truck mix)		0.0784	9.408	94.2%	0.55	2.39
		Total:	31.92		1.67	7.33

Notes:

1.) Emission factor for Cement Storage Bin 1 and 2 and Cement Batcher from vendor (CON-E-CO). Emission factors for other emission sources from AP-42 Chapter 11.12 "Concrete Batching".

Concrete Capacity and Composition Information

Maximum Capacity:

120 yd3 concrete/hr

Assumed Concrete Composition (1 yd3):

1865 lbs coarse aggregate

1428 lbs sand

491 lbs cement

73 lbs cement supplement

4024 lbs total

Ton material/120 yd³ concrete:

111.90 ton coarse aggregate

85.68 ton sand

29.46 ton cement

4.38 ton cement supplement

231.42 ton total

Toxic Air Pollutant Emission Calculations

Temporary Concrete Batch Plant, Mountain Home, Idaho Romero General Construction Corp.

	Α	S	В	е	C	d	С	r	Cr(VI)
	EF	Emissions	EF	Emissions	EF	Emissions	EF	Emissions	EF	Emissions
Source	(lb/ton)	(lb/hr)	(lb/ton)	(lb/hr)	(lb/ton)	(lb/hr)	(lb/ton)	(lb/hr)	(lb/ton)	(lb/hr)
Cement Storage 1 Bin	1.00E-06	2.95E-05	9.04E-08	2.66E-06	1.98E-10	5.83E-09	1.22E-06	3.59E-05	3.66E-07	1.08E-05
Cement Storage 2 Bin	4.24E-09	1.86E-08	4.86E-10	2.13E-09	4.86E-10	2.13E-09	2.90E-08	1.27E-07	5.80E-09	2.54E-08
Cement Batcher (weigh hopper)										
Aggregate delivery to ground storage										
Sand delivery to ground storage										
Aggregate transfer to conveyor										
Sand transfer to conveyor										
Truck loading (truck mix)	1.16E-06	3.93E-05	1.04E-07	3.52E-06	9.06E-09	3.07E-07	4.10E-06	1.39E-04	8.20E-07	2.77E-05
Total		6.87E-05		6.18E-06		3.15E-07		1.75E-04		3.86E-05
EL		1.50E-06		2.80E-05		3.70E-06			****	5.60E-07
Model?		yes		no		no		see Cr (VI)		yes

	Mn		Ni		P		Se	
	EF	Emissions	EF	Emissions	EF	Emissions	EF	Emissions
Source	(lb/ton)	(lb/hr)	(lb/ton)	(lb/hr)	(lb/ton)	(lb/hr)	(lb/ton)	(lb/hr)
Cement Storage 1 Bin	2.56E-07	7.54E-06	2.28E-06	6.72E-05	3.54E-06	1.04E-04	7.24E-08	2.13E-06
Cement Storage 2 Bin	1.17E-07	5.12E-07	4.18E-08	1.83E-07	ND		ND	
Cement Batcher (weigh hopper)								
Aggregate delivery to ground storage								
Sand delivery to ground storage								
Aggregate transfer to conveyor								
Sand transfer to conveyor		<u></u>						
Truck loading (truck mix)	2.08E-05	7.04E-04	4.78E-06	1.62E-04	1.23E-05	4.16E-04	1.13E-07	3.82E-06
Total		7.12E-04		2.29E-04		5.21E-04		5.96E-06
EL EL		3.33E-01		2.70E-05		7.00E-03		1.30E-02
Model?		no		yes		no		no

Notes:

- 1.) Emission Factors from AP-42 Chapter 11.12 "Concrete Batching", Table 11.12-8.
- 2.) Emission Limits (EL) from IDAPA 58.01.01.585 and 586.
- 3.) Modeling performed for Toxic Air Pollutants (TAPs) emission rates that exceeded the EL.

Air Pollutant Emissions Electricity Generator

Combustion Source Characteristics Stack Data Genset Manufacturer MQ Power Stack Height (ft) 5.0 Genset Model DCA180SSJ Stack Diameter (ft) 0.38 Exit Gas Temperature (°F)° **Engine Manufacturer** John Deere 800 6066HF485 Wet Actual Flow Rate (acfm) **Engine Model** 1,371 Wet Standard Flow Rate (wscfm) Break Horsepower (bhp) 315 251 Power Generation (kW - prime) 144 Dry Standard Flow Rate (dscfm) 224 Fuel Grain Loading Flow Rate (dscfm) 290 Diesel Max Hourly Fuel Consumption (gal/hr) 11.4 Stack Velocity (m/s) 63.04 Fd (dscf stack gas/10⁶ BTU) Heating Value (BTU/gal) 128,000 9.190 Fw (wscf stack gas/10⁶ BTU) Heat Input Capacity (BTU/hr) 1,459,200 10,320 Miscellaneous Support Data Pressure at Standard Conditions (atm) 1 Temperature at Standard Conditions (K) 293 Ideal Gas Constant (atm-ft³/mol-K) 1.314 Mountain Home Barometric Pressure (atm) 0.90

Criteria Pollutants	der Villagenbeit arbeiten. Die eine						
1 Dolly-tont	Emission Factor ^a	Emission	Potential Emissions	Potential Emissions	Potential Emissions		
Pollutant PM ₁₀ (assume = PM)		Factor Unit	(lb/hr)	(TPY)	(g/s)		
	0.08	g/bhp-hr	5.56E-02	0.24	0.007		
SO ₂	2.05E-03	lb/bhp-hr	0.65	2.83	0.081		
NO _x	2.53	g/bhp-hr	1.76	7.70	0.221		
со	0.45	g/bhp-hr	0.31	1.37	0.039		
VOC	2.47E-03	lb/bhp-hr	0.78	3.41	0.098		

PM Grain Loading Stand	TRUE TO CHARLEST			
Pollutant	Potential Emissions (lb/hr)	Grain Load @ 3% Oxygen (gr/dscf)	PM Grain Standard ^b (gr/dscf)	Meets Standard?
PM	0.056	0.022	0.05	yes

Notes:

- (a) Emission factors for PM, CO, and NOx supplied by the vendor (MQ Power). Emission factors for SO₂ and VOC from AP-42 Chapter 3.3, "Gasoline and Diesel Industrial Engines" Table 3.3-1.
- (b) IDAPA 58.01.01.677.
- (c) The discharge temperature for the generator exhaust was reduced from 905 to 800 °F to account for heat losses from exhaust manifold to discharge elevation.