



STATE OF IDAHO  
DEPARTMENT OF  
ENVIRONMENTAL QUALITY

1410 North Hilton • Boise, Idaho 83706 • (208) 373-0502  
www.deq.idaho.gov

C.L. "Butch" Otter, Governor  
John H. Tippets, Director

May 11, 2018

Shawn Parker, Area Manager  
Staker & Parson Companies dba Idaho Materials & Construction 00281  
1310 Addison Ave. W.  
Twin Falls, ID 83301

RE: Facility ID No., 777-00281, Project No. 62059, Staker & Parson Companies dba Idaho  
Materials & Construction 00281, Portable  
Transfer of Ownership by Permit to Construct Revision

Dear Mr. Parker:

The Department of Environmental Quality (DEQ) is issuing Permit to Construct (PTC) No. P-2011.0099, Project 62059, to Staker & Parson Companies dba Idaho Materials & Construction 00281, located in Twin Falls for a transfer of ownership. This PTC permit is issued in accordance with IDAPA 58.01.01.209.04 of the Rules for the Control of Air Pollution in Idaho and is based on the certified information received on April 24, 2018. The transfer of ownership is based on the following information:

**Previous Permittee Information**

Permittee:	Lakeside Industries dba Valley Paving 00281
Mailing Address:	85 Walker Rd., Bellvue, ID 83313
Facility Location:	Portable
Facility Contact:	Karen Garnes, Environmental Program Director
Phone Number:	(425) 313-2660
E-mail Address:	kareng@lakesideind.com
Responsible Official:	Karen Garnes, Environmental Program Director
Phone Number:	(425) 313-2660

**Updated Permittee Information**

Permittee:	Staker & Parson Companies dba Idaho Materials & Construction 00281
Mailing Address:	1310 Addison Ave. W., Twin Falls, ID 83301
Facility Location:	Portable
Facility Contact:	Shawn Parker, Area Manager
Phone Number:	(208) 733-5933
E-mail Address:	shawn.parker@idahomaterials.com
Responsible Official:	Shawn Parker, Area Manager
Phone Number:	(208) 733-5933

This permit is effective immediately and replaces PTC No. P-2011.0099, Project 61457, issued April 1, 2015. This permit does not release Staker & Parson Companies dba Idaho Materials & Construction 00281 from compliance with all other applicable federal, state, or local laws, regulations, permits, or ordinances.

In order to fully understand the compliance requirements of this permit, DEQ highly recommends that you schedule a meeting with Bobby Dye, Regional Air Quality and Remediation Manager, at (208) 737-3889 to review and discuss the terms and conditions of this permit. Should you choose to schedule this meeting, DEQ recommends that the following representatives attend the meeting: your facility's plant manager, responsible official, environmental contact, and any other staff responsible for day-to-day compliance with permit conditions.

If you have any questions, please contact Tom Burnham at 208.373.0477 or [tom.burnham@deq.idaho.gov](mailto:tom.burnham@deq.idaho.gov).

Sincerely,

A handwritten signature in black ink, appearing to read "Mike Simon". The signature is fluid and cursive, written over a white background.

Mike Simon  
Stationary Source Program Manager  
Air Quality Division

Attachment

MS/tb

Permit No. P-2011.0099 PROJ 62059

## Air Quality

### PERMIT TO CONSTRUCT

---

**Permittee** Staker & Parson Companies dba Idaho Materials & Construction 00281  
**Permit Number** P-2011.0099  
**Project ID** 62059  
**Facility ID** 777-00281  
**Facility Location** Portable throughout the state of Idaho

### Permit Authority

This permit (a) is issued according to the "Rules for the Control of Air Pollution in Idaho" (Rules), IDAPA 58.01.01.200–228; (b) pertains only to emissions of air contaminants regulated by the State of Idaho and to the sources specifically allowed to be constructed or modified by this permit; (c) has been granted on the basis of design information presented with the application; (d) does not affect the title of the premises upon which the equipment is to be located; (e) does not release the permittee from any liability for any loss due to damage to person or property caused by, resulting from, or arising out of the design, installation, maintenance, or operation of the proposed equipment; (f) does not release the permittee from compliance with other applicable federal, state, tribal, or local laws, regulations, or ordinances; and (g) in no manner implies or suggests that the Idaho Department of Environmental Quality (DEQ) or its officers, agents, or employees assume any liability, directly or indirectly, for any loss due to damage to person or property caused by, resulting from, or arising out of design, installation, maintenance, or operation of the proposed equipment. Changes in design, equipment, or operations may be considered a modification subject to DEQ review in accordance with IDAPA 58.01.01.200–228.

**Date Issued** May 11, 2018



Tom Burnham, Permit Writer



Mike Simon, Stationary Source Manager

## Contents

1	Permit Scope.....	3
2	Facility-Wide Conditions .....	4
3	Asphalt Production Equipment.....	7
4	General Provisions.....	13

# 1 Permit Scope

## Purpose

- 1.1 This is a revised permit to construct (PTC) to change the name from Lakeside Industries dba Valley Paving 00281 to Staker & Parson Companies dba Idaho Materials & Construction 00281.
- 1.2 This PTC replaces Permit to Construct No. P-2011.0099, issued on April 1, 2015.

## Regulated Sources

Table 1.1 lists all sources of regulated emissions in this permit.

**Table 1.1 Regulated Sources**

Permit Section	Source	Control Equipment
1	<u>Material Transfer Points:</u> Materials handling Asphalt aggregate transfers Truck unloading of aggregate Aggregate conveyor transfers Aggregate handling	Fugitive Emissions Controls
2	<u>Asphalt Drum Mixer:</u> Manufacturer: H&R Mechanical Model: N/A Type: Counter-flow Manufacture Date: 2015 Max. production: 134 T/hr Burner Manufacturer: Gencor Burner Model: UF-70H Max. Heat Input: 86 MMBtu/hr Fuel(s): Natural gas only	<u>Asphalt Drum Mixer Baghouse:</u> Manufacturer: Gencor Model: 121 Pulse Jet Baghouse Type: Reverse pulse-jet Flow rate: 7,900 dscfm PM <sub>10</sub> control efficiency: 99%

[4/1/2015]

## 2 Facility-Wide Conditions

### Fugitive Dust Control

#### 2.1 Reasonable Control of Fugitive Emissions

In accordance with IDAPA 58.01.01.650-651, all reasonable precautions shall be taken to prevent particulate matter from becoming airborne.

The permittee shall monitor and maintain records of the frequency and the method(s) used (e.g., water, chemical dust suppressants) to reasonably control fugitive dust emissions.

The permittee shall maintain records of all fugitive dust complaints received. The permittee shall take appropriate corrective action as expeditiously as practicable after receipt of a valid complaint. The records shall include, at a minimum, the date that each complaint was received and a description of the following: the complaint, the permittee's assessment of the validity of the complaint, any corrective action taken, and the date the corrective action was taken.

The permittee shall conduct a daily facility-wide inspection of potential sources of fugitive dust emissions, during daylight hours and under normal operating conditions to ensure that the methods used to reasonably control fugitive dust emissions are effective. If fugitive dust emissions are not being reasonably controlled, the permittee shall take corrective action as expeditiously as practicable. The permittee shall maintain records of the results of each fugitive dust emissions inspection. The records shall include, at a minimum, the date of each inspection and a description of the following: the permittee's assessment of the conditions existing at the time fugitive emissions were present (if observed), any corrective action taken in response to the fugitive dust emissions, and the date the corrective action was taken.

[4/1/2015]

#### 2.2 Fugitive Emissions Controls

In accordance with IDAPA 58.01.01.808.01 and 808.02, the asphalt plant shall employ efficient fugitive dust controls. The control shall be employed and maintained in such a manner as to satisfactorily control the emission of particulate material from any point other than a stack outlet. These controls include, but are not limited to the:

- Maintaining the moisture content in ¼" or smaller aggregate material at 1.5% by weight, by using water sprays, by using shrouds, or other emissions controls. If this fugitive dust control is employed at this facility the Permittee shall measure the moisture content of smaller aggregate on a weekly basis. In addition, records shall be maintained to demonstrate compliance with this selected method.
- Aggregate Weigh Conveyor(s) - Transfer from the bins to the conveyors and from the conveyors to the scalping screens. If this fugitive dust control is employed at this facility the Permittee shall be able to demonstrate this to DEQ staff.
- Aggregate Scalping Screen(s) - Aggregate flow across the scalping screen onto the conveyors. If this fugitive dust control is employed at this facility the Permittee shall be able to demonstrate this to DEQ staff.
- Aggregate Conveyor(s) to the Asphalt Drum Mixer (e.g., opening of the drum) - Aggregate transfer from the conveyors to the asphalt drum mixer. If this fugitive dust control is employed at this facility the Permittee shall be able to demonstrate this to DEQ staff.

- Operate with a covered conveyor(s) from the asphalt drum mixer to the silo fill transfer point, or if loaded directly into the truck, from the asphalt drum mixer to the truck load out transfer point. If this fugitive dust control is employed at this facility the Permittee shall be able to demonstrate this to DEQ staff.
- Good operating practices, including water spraying or other suitable measures, shall be employed to prevent dust generation and atmospheric entrainment during operations such as stockpiling, screen changing and general maintenance. The Permittee shall be able to demonstrate this to DEQ staff.

[4/1/2015]

## **Relocation Requirements**

### **2.3 Collocation Restrictions**

This asphalt plant shall only collocate with either one (1) portable rock crushing plant, one (1) portable concrete batch plant, or one (1) other portable hot mix asphalt plant when operating within attainment or unclassified areas and the other plant is permitted to specifically allow collocation. Collocation is defined as being within 1,000 feet ( $\pm$  6 feet) of this asphalt plant.

### **2.4 Relocation Requirements**

In accordance with IDAPA 58.01.01.500, at least 10 days prior to relocating any of the permitted equipment, the permittee shall submit a completed DEQ Portable Equipment Relocation Form (PERF) to the following address or fax number:

PERF Processing Unit  
 DEQ – Air Quality  
 1410 N. Hilton  
 Boise, ID 83706-1255  
 Ph.: (208) 373-0502  
 Fax: (208) 373-0340

## **Non-attainment Area Operations**

### **2.5 Non-attainment Area Operations**

This asphalt plant shall not collocate with another hot-mix asphalt plant, concrete batch plant, or rock crushing plant when located in any PM<sub>10</sub> non-attainment area or proposed PM<sub>10</sub> non-attainment area, without obtaining a permit which specifically allows for collocation in a non-attainment area.

This asphalt plant shall not exceed a maximum of nine hundred and one tons per day (901 T/day). This asphalt plant shall not exceed a maximum of three hundred eight thousand, nine hundred seventy two tons in any consecutive 12-month period (328,972 T/yr) when located in any PM<sub>10</sub> non-attainment area or proposed PM<sub>10</sub> non-attainment area.

## **Odors**

### **2.6 Odors**

The permittee shall not allow, suffer, cause, or permit the emission of odorous gases, liquids, or solids into the atmosphere in such quantities as to cause air pollution in accordance with IDAPA 58.01.01.776.01.

## **Monitoring and Recordkeeping Requirements**

### **2.7 Fugitive Dust Monitoring and Recordkeeping**

The permittee shall conduct a facility-wide inspection of potential sources of visible fugitive emissions during daylight hours and under normal operating conditions once each day that the asphalt plant operates, to demonstrate compliance with the Reasonable Control of Fugitive Emissions and the Fugitive Emissions Controls permit conditions. The inspection shall consist of a see/no see evaluation for each potential source of visible fugitive emissions. If any visible fugitive emissions are present from any source of fugitive emissions, the permittee shall take appropriate corrective action as expeditiously as practicable to mitigate the visible fugitive emissions.

The permittee shall maintain records of the results of each see/no see evaluation of visible fugitive emissions inspection. The records shall include, at a minimum, the date and results of each inspection and a description of the following: the permittee's assessment of the conditions existing at the time visible fugitive emissions are present (if observed), any corrective action taken in response to the visible fugitive emissions, and the date corrective action was taken.

### **2.8 Collocation Demonstration Recordkeeping**

To demonstrate compliance with the collocation requirements at each site the permitted equipment operates, the permittee shall measure and record the minimum distances, to an accuracy of plus or minus six feet, from the exhaust stacks of the asphalt drum mixer to the nearest asphalt plant, concrete batch plant, or rock crushing plant. This procedure shall be conducted each time the permitted portable equipment changes location. Measurements greater than 1,100 feet may be recorded as greater than 1,100 feet.

[10/17/2011]

### **2.9 Odor Complaints**

The permittee shall maintain records of all odor complaints received to demonstrate compliance with the Odors permit condition. The permittee shall take appropriate corrective action as expeditiously as practicable. The records shall include, at a minimum, the date each complaint was received and a description of the following: the complaint, the permittee's assessment of the validity of the complaint, any corrective action taken, and the date the corrective action was taken.

### **2.10 Recordkeeping**

All monitoring and recordkeeping documentation required by this permit shall be maintained in accordance with the Recordkeeping general provision.

[4/1/2015]

### 3 Asphalt Production Equipment

#### Process Description

##### 3.1 Process Description

Asphalt is made at the facility as follows. First, stockpiled aggregate is transferred to feed bins. The Applicant has also requested that recycled asphalt pavement (RAP) be used in the aggregate. Aggregate is then dispensed from the feed bins onto feeder conveyors, which transfer the aggregate to the asphalt drum mixer. The Applicant has requested that the asphalt drum mixer be fired on natural gas only. Next, aggregate travels through the rotating drum mixer, and when dried and heated, it is mixed with hot liquid asphaltic oil. The resulting asphalt is conveyed to hot storage bins until it can be loaded into trucks for transport off site or transferred to silos for temporary storage prior to transport off-site.

##### 3.2 Control Device Descriptions

Table 3.1 Asphalt Production Equipment Description

Emissions Units / Processes	Control Devices	Emission Points
Asphalt drum mixer	Asphalt drum mixer baghouse	Asphalt drum mixer baghouse exhaust stack

[10/17/2011]

#### Emission Limits

##### 3.3 Emission Limits

The emissions from the asphalt drum mixer baghouse stack shall not exceed any emissions rate limit in the following table.

Table 3.2 Asphalt Production Equipment Emission Limits<sup>a</sup>

Source Description	PM <sub>10</sub> <sup>(b)</sup>		CO
	lb/hr <sup>(c)</sup>	T/yr <sup>(d)</sup>	T/yr <sup>(d)</sup>
Asphalt drum mixer	3.11	6.1	56

- a In absence of any other credible evidence, compliance is ensured by complying with permit operating, monitoring, and record keeping requirements.
- b Particulate matter with an aerodynamic diameter less than or equal to a nominal ten (10) micrometers, including condensable particulate as defined in IDAPA 58.01.01.006.
- c Pounds per hour, as determined by a test method prescribed by IDAPA 58.01.01.157, EPA reference test method, continuous emission monitoring system (CEMS) data, or DEQ-approved alternative.
- d Tons per any consecutive 12-calendar month period.

[10/17/2011]

##### 3.4 40 CFR 60, Subpart I – Standard for Particulate Matter

In accordance with 40 CFR 60.92, the emissions from the asphalt drum mixer baghouse stack shall not exceed:

- Particulate matter in excess of 0.04 gr/dscf (90 mg/dscm)
- 20% opacity

### 3.5 Opacity Limit

Visible emissions from the asphalt drum mixer baghouse stack, the asphaltic oil tank heater stack, the load-out station, and the silo filling slat conveyor, or any other stack, vent, or functionally equivalent opening associated with the asphalt drum mixer baghouse, the asphaltic oil tank heater, the load-out station, and the silo filling slat conveyor processes, shall not exceed 20% opacity for a period or periods aggregating more than three minutes in any 60-minute period as required by IDAPA 58.01.01.625. Opacity shall be determined by the procedures contained in IDAPA 58.01.01.625.

[10/17/2011]

## Operating Requirements

### 3.6 Asphalt Production Limits

Asphalt production from this facility shall not exceed the following limits:

Table 3.3 Asphalt Production Limits

Location/Collocation	Asphalt Production Limit (T/yr) <sup>a</sup>	Asphalt Production Limit (T/day)	Asphalt Production Limit (T/hr)
Located in Attainment Areas	525,756	N/A	134
Located in Non-Attainment Areas	328,972	901	134
Collocated w/ Another Plant	262,878	N/A	134

a Tons per year (T/yr) is defined as tons of material processed per consecutive 12-calendar month period.

### 3.7 Allowable Raw Materials

This facility shall process only aggregate, asphaltic oil, anti-stripping additives (e.g. Superbond®), and RAP as raw materials to make asphalt. RAP use shall not exceed 50%, by weight, of the asphalt produced.

[4/1/2015]

### 3.8 Baghouse System Control Equipment

The permittee shall install, operate, and maintain a baghouse to control emissions from the asphalt drum mixer. The collected particulate from the baghouse shall be routed to the asphalt drum mixer for incorporation into the final asphalt product.

[10/17/2011]

## Fuel Specifications

### 3.9 Asphalt Drum Mixer Fuel Specifications

Asphalt Drum Mixer Fuel Specifications

The asphalt drum mixer shall only combust the following fuel:

- Natural gas

## Performance Testing Requirements

### 3.10 PM<sub>10</sub> and Opacity Performance Testing

Performance testing on the asphalt drum mixer baghouse stack may be performed concurrently with the initial performance test required by Initial 40 CFR 60, Subpart I – Standard for Particulate Matter Performance Test permit condition. Testing must occur within 180 days of permit issuance and no less than once every five years following the date the initial performance test was performed. The most recent test was conducted May 22, 2014.

The performance test shall measure the PM<sub>10</sub> emission rate in pounds per hour and the opacity to demonstrate compliance with the PM<sub>10</sub> Emissions Limit and Opacity Limit permit conditions.

The performance test shall be conducted under worst-case normal operating conditions and in accordance with IDAPA 58.01.01.157, and Performance Testing General Provision of this permit. The permittee is encouraged to submit a performance testing protocol for approval 30 days prior to conducting the performance tests.

[4/1/2015]

### **3.11 PM<sub>10</sub> and Opacity Performance Testing Methods and Procedures**

The permittee shall use EPA Methods 5 and 202, or EPA Methods 201A and 202, or such comparable and equivalent methods approved in accordance with Subsection 157.02.d, to determine compliance with the PM<sub>10</sub> Emissions Limit permit condition.

The permittee shall use EPA Method 9 to determine compliance with the Opacity Limit permit condition with the method of calculating opacity exceedances altered in accordance with IDAPA 58.01.01.625.04.

[4/1/2015]

### **3.12 Performance Test Monitoring and Recordkeeping**

The permittee shall monitor and record the following during each performance test:

- The asphalt production rate, in tons per hour, at least once every 15 minutes,
- The visible emissions observed,
- The RAP percentage usage,
- The fuel combusted in the asphalt drum mixer,
- The applicable emissions control device operating parameters at least once every 15 minutes.

[4/1/2015]

## **Monitoring and Recordkeeping Requirements**

### **3.13 Asphalt Production Recordkeeping**

For each day that the asphalt drum mixer is operated the Permittee shall maintain the following records:

- The amount of asphalt produced in tons per hour and tons per day to demonstrate compliance with the hourly and daily Asphalt Production Limits permit conditions.

Monthly asphalt production shall be determined by summing daily production over the previous calendar month. Consecutive 12-months of asphalt production shall be determined by summing the monthly production over the previous consecutive 12 month period to demonstrate compliance with the consecutive 12-months Asphalt Production Limits permit condition.

[10/17/2011]

### **3.14 RAP Weight Percentage Recordkeeping**

For each day that the asphalt drum mixer is operated using RAP, the Permittee shall record the amount of RAP used and the total weight of asphalt produced, either on a daily or per batch basis, to demonstrate compliance with the Allowable Raw Materials permit condition.

The weight percentage of RAP used shall be calculated as follows:

$$\text{Weight percentage of RAP} = \frac{\text{RAP material used (either per daily or per batch, tons-RAP)}}{\text{total asphalt produced (either per day or per batch, tons-asphalt)}} \times 100$$

[4/1/2015]

### **3.15 Baghouse/Filter System Procedures**

Within 60 days of permit issuance, the permittee shall have developed a Baghouse Filter System Procedures document for the inspection and operation of the baghouse filter system which controls particulate matter emissions from the asphalt drum mixer. The Baghouse Filter System Procedures document shall be a permittee-developed document independent of the manufacturer supplied operating manual but may include summaries of procedures included in the manufacturer supplied operating manual.

The Baghouse Filter System Procedures document shall describe the procedures that will be followed to comply with the General Compliance General Provisions and shall contain requirements for monthly see/no-see visible emissions inspections of the baghouse. The inspection shall occur during daylight hours and under normal operating conditions.

The Baghouse/Filter System Procedures document shall include a schedule and procedures for corrective action that will be taken if visible emissions are present from the asphalt drum mixer baghouse at any time. At a minimum the document shall include:

- Procedures to determine if bags or cartridges are ruptured; and
- Procedures to determine if bags or cartridges are not appropriately secured in place.

The permittee shall maintain records of the results of each baghouse filter system inspection. The records shall include, but not be limited to, the following:

- Date and time of inspection,
- Equipment inspected (e.g. exterior housing of baghouse, fan motor, auger, inlet air ducting);
- Description of whether visible emissions were present, and if visible emissions were present a description of the corrective action that was taken.
- Date corrective action was taken.

The Baghouse Filter System Procedures document shall be submitted to DEQ within 60 days after permit issuance and shall contain a certification by a responsible official. Any changes to the Baghouse Filter System Procedures document shall be submitted within 15 days of the change.

The Baghouse Filter System Procedures document shall remain on-site at all times and shall be made available to DEQ representatives upon request.

The operating, monitoring, and recordkeeping requirements specified in the Baghouse Filter System Procedures document are incorporated by reference into this permit and are enforceable permit conditions.

### **3.16 Recordkeeping**

All monitoring and recordkeeping documentation required by this permit shall be maintained in accordance with the Recordkeeping general provision.

[4/1/2015]



**Table 3.4 NSPS 40 CFR 60, Subpart A – Summary of General Provisions for Owners and Operators of Affected Facilities  
(continued)**

Section	Subject	Summary of Section Requirements
60.7(a), (b), and (f)	Notification and Recordkeeping	<ul style="list-style-type: none"> <li>• Notification shall be furnished of commencement of construction postmarked no later than 30 days of such date.</li> <li>• Notification shall be furnished of initial startup postmarked within 15 days of such date.</li> <li>• Notification shall be furnished of any physical or operational change that may increase emissions postmarked 60 days before the change is made.</li> <li>• Records shall be maintained of the occurrence and duration of any startup, shutdown or malfunction; any malfunction of the air pollution control equipment; or any periods during which a CMS or monitoring device is inoperative.</li> <li>• Records shall be maintained, in a permanent form suitable for inspection, of all measurements, performance testing measurements, calibration checks, adjustments and maintenance performed, and other required information. Records shall be maintained for a period of two years following the date of such measurements, maintenance, reports, and records.</li> </ul>
60.8	Performance Tests	<ul style="list-style-type: none"> <li>• At least 30 days prior notice of any performance test shall be provided to afford the opportunity to have an observer to be present.</li> <li>• Within 60 days of achieving the maximum production rate, but not later 180 days after initial startup, performance test(s) shall be conducted and a written report of the results of such test(s) furnished.</li> <li>• Performance testing facilities shall be provided as follows: <ul style="list-style-type: none"> <li>Sampling ports adequate for test methods applicable to such facility.</li> <li>Safe sampling platform(s).</li> <li>Safe access to sampling platform(s).</li> <li>Utilities for sampling and testing equipment.</li> </ul> </li> <li>• Performance tests shall be conducted and data reduced in accordance with 40 CFR 60.8(b), (c), and (f).</li> </ul>
60.11(a), (d), (f), and (g)	Compliance with Standards and Maintenance Requirements	<ul style="list-style-type: none"> <li>• When performance tests are required, compliance with standards is determined by methods and procedures established by 40 CFR 60.8.</li> <li>• At all times, including periods of startup, shutdown, and malfunction, the owners and operators shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with good air pollution control practice for minimizing emissions.</li> <li>• For the purpose of submitting compliance certifications or establishing whether or not a person has violated or is in violation of any standard, nothing shall preclude the use, including the exclusive use, of any credible evidence or information, relevant to whether a source would have been in compliance with applicable requirements if the appropriate performance or compliance test or procedure had been performed.</li> </ul>
60.12	Circumvention	<ul style="list-style-type: none"> <li>• No permittee shall build, erect, install, or use any article, machine, equipment or process, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard.</li> </ul>
60.14	Modification	<ul style="list-style-type: none"> <li>• A physical or operational change which results in an increase in the emission rate to the atmosphere or any pollutant to which a standard applies shall be considered a modification, and upon modification an existing facility shall become an affected facility in accordance with the requirements and exemptions in 40 CFR 60.14.</li> <li>• Within 180 days of the completion of any physical or operational change, compliance with all applicable standards must be achieved.</li> </ul>
60.15	Reconstruction	<ul style="list-style-type: none"> <li>• An existing facility, upon reconstruction, becomes an affected facility, irrespective of any change in emission rate in accordance with the requirements of 40 CFR 60.15.</li> </ul>

## 4 General Provisions

### General Compliance

4.1 The permittee has a continuing duty to comply with all terms and conditions of this permit. All emissions authorized herein shall be consistent with the terms and conditions of this permit and the "Rules for the Control of Air Pollution in Idaho." The emissions of any pollutant in excess of the limitations specified herein, or noncompliance with any other condition or limitation contained in this permit, shall constitute a violation of this permit, the "Rules for the Control of Air Pollution in Idaho," and the Environmental Protection and Health Act (Idaho Code §39-101, et seq.)

[Idaho Code §39-101, et seq.]

4.2 The permittee shall at all times (except as provided in the "Rules for the Control of Air Pollution in Idaho") maintain in good working order and operate as efficiently as practicable all treatment or control facilities or systems installed or used to achieve compliance with the terms and conditions of this permit and other applicable Idaho laws for the control of air pollution.

[IDAPA 58.01.01.211, 5/1/94]

4.3 Nothing in this permit is intended to relieve or exempt the permittee from the responsibility to comply with all applicable local, state, or federal statutes, rules, and regulations.

[IDAPA 58.01.01.212.01, 5/1/94]

### Inspection and Entry

4.4 Upon presentation of credentials, the permittee shall allow DEQ or an authorized representative of DEQ to do the following:

- Enter upon the permittee's premises where an emissions source is located, emissions-related activity is conducted, or where records are kept under conditions of this permit;
- Have access to and copy, at reasonable times, any records that are kept under the conditions of this permit;
- Inspect at reasonable times any facilities, equipment (including monitoring and air pollution control equipment), practices, or operations regulated or required under this permit; and
- As authorized by the Idaho Environmental Protection and Health Act, sample or monitor, at reasonable times, substances or parameters for the purpose of determining or ensuring compliance with this permit or applicable requirements.

[Idaho Code §39-108]

### Construction and Operation Notification

4.5 This permit shall expire if construction has not begun within two years of its issue date, or if construction is suspended for one year.

[IDAPA 58.01.01.211.02, 5/1/94]

4.6 The permittee shall furnish DEQ written notifications as follows:

- A notification of the date of initiation of construction, within five working days after occurrence; except in the case where pre-permit construction approval has been granted then notification shall be made within five working days after occurrence or within five working days after permit issuance whichever is later;

- A notification of the date of any suspension of construction, if such suspension lasts for one year or more; and
- A notification of the initial date of achieving the maximum production rate, within five working days after occurrence - production rate and date.

[IDAPA 58.01.01.211.01, 5/1/94]

- A notification of the anticipated date of initial start-up of the stationary source or facility not more than sixty days or less than thirty days prior to such date; and
- A notification of the actual date of initial start-up of the stationary source or facility within fifteen days after such date.

[IDAPA 58.01.01.211.03, 5/1/94]

## **Performance Testing**

4.7 If performance testing (air emissions source test) is required by this permit, the permittee shall provide notice of intent to test to DEQ at least 15 days prior to the scheduled test date or shorter time period as approved by DEQ. DEQ may, at its option, have an observer present at any emissions tests conducted on a source. DEQ requests that such testing not be performed on weekends or state holidays.

4.8 All performance testing shall be conducted in accordance with the procedures in IDAPA 58.01.01.157. Without prior DEQ approval, any alternative testing is conducted solely at the permittee's risk. If the permittee fails to obtain prior written approval by DEQ for any testing deviations, DEQ may determine that the testing does not satisfy the testing requirements. Therefore, at least 30 days prior to conducting any performance test, the permittee is encouraged to submit a performance test protocol to DEQ for approval. The written protocol shall include a description of the test method(s) to be used, an explanation of any or unusual circumstances regarding the proposed test, and the proposed test schedule for conducting and reporting the test.

4.9 Within 60 days following the date in which a performance test required by this permit is concluded, the permittee shall submit to DEQ a performance test report. The written report shall include a description of the process, identification of the test method(s) used, equipment used, all process operating data collected during the test period, and test results, as well as raw test data and associated documentation, including any approved test protocol.

[IDAPA 58.01.01.157, 4/5/00]

## **Monitoring and Recordkeeping**

4.10 The permittee shall maintain sufficient records to ensure compliance with all of the terms and conditions of this permit. Monitoring records shall include, but not be limited to, the following: (a) the date, place, and times of sampling or measurements; (b) the date analyses were performed; (c) the company or entity that performed the analyses; (d) the analytical techniques or methods used; (e) the results of such analyses; and (f) the operating conditions existing at the time of sampling or measurement. All monitoring records and support information shall be retained for a period of at least five years from the date of the monitoring sample, measurement, report, or application. Supporting information includes, but is not limited to, all calibration and maintenance records, all original strip-chart recordings for continuous monitoring instrumentation, and copies of all reports required by this permit. All records required to be maintained by this permit shall be made available in either hard copy or electronic format to DEQ representatives upon request.

[IDAPA 58.01.01.211, 5/1/94]

## **Excess Emissions**

- 4.11 The permittee shall comply with the procedures and requirements of IDAPA 58.01.01.130–136 for excess emissions due to start-up, shut-down, scheduled maintenance, safety measures, upsets, and breakdowns.

[IDAPA 58.01.01.130–136, 4/5/00]

## **Certification**

- 4.12 All documents submitted to DEQ—including, but not limited to, records, monitoring data, supporting information, requests for confidential treatment, testing reports, or compliance certification—shall contain a certification by a responsible official. The certification shall state that, based on information and belief formed after reasonable inquiry, the statements and information in the document(s) are true, accurate, and complete.

[IDAPA 58.01.01.123, 5/1/94]

## **False Statements**

- 4.13 No person shall knowingly make any false statement, representation, or certification in any form, notice, or report required under this permit or any applicable rule or order in force pursuant thereto.

[IDAPA 58.01.01.125, 3/23/98]

## **Tampering**

- 4.14 No person shall knowingly render inaccurate any monitoring device or method required under this permit or any applicable rule or order in force pursuant thereto.

[IDAPA 58.01.01.126, 3/23/98]

## **Transferability**

- 4.15 This permit is transferable in accordance with procedures listed in IDAPA 58.01.01.209.06.

[IDAPA 58.01.01.209.06, 4/11/06]

## **Severability**

- 4.16 The provisions of this permit are severable, and if any provision of this permit to any circumstance is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

[IDAPA 58.01.01.211, 5/1/94]