



STATE OF IDAHO
DEPARTMENT OF
ENVIRONMENTAL QUALITY

650 Addison Avenue West, Suite 110 • Twin Falls, Idaho 83301 • (208) 736-2190
www.deq.idaho.gov

Governor Brad Little
Director John H. Tippetts

December 17, 2019

Mr. Mark Mitton, City Administrator and
Mr. David Waldron, P.E., City Engineer
P.O. Box 1090
Burley, Idaho 83318

Re: NWW-2019-00567, City of Burley IC Park Bank Stabilization 401 Certification

Dear Mr. Mitton and Mr. Waldron:

The Idaho Department of Environmental Quality (DEQ) has considered water quality certification for the above referenced project. Public comment occurred from November 22, 2019 through December 16, 2019. No public comments were submitted. Therefore, DEQ is issuing the attached 401 water quality certification subject to the terms and conditions contained therein.

If you have any concerns or questions, please contact Dr. Balthasar Buhidar at (208) 736-2190 or at Balthasar.buhidar@deq.idaho.gov.

Sincerely,

A handwritten signature in blue ink that reads "Sue Switzer".

Sue Switzer
Regional Administrator
Twin Falls Regional Administrator

BBB/sh

c: Christen Marve Griffith, USACOE – Boise Regulatory Office
Loren Moore, DEQ State Office



Idaho Department of Environmental Quality Final §401 Water Quality Certification

December 17, 2019

404 Permit Application Number: NWW-2019-00567, IC Park Bank Stabilization

Joint Application Number: 13, Bank Stabilization

Applicant/Authorized Agent: City of Burley / Mark Mitton (City of Burley)

Project Location: Latitude 42.5510° N, Longitude -113.7971 W; 300 West Hampton Drive, Burley, Idaho 83318; Cassia County

Receiving Water Body: Snake River in Milner Reservoir

Pursuant to the provisions of Section 401(a)(1) of the Federal Water Pollution Control Act (Clean Water Act), as amended; 33 U.S.C. Section 1341(a)(1); and Idaho Code §§ 39-101 et seq. and 39-3601 et seq., the Idaho Department of Environmental Quality (DEQ) has authority to review activities receiving Section 404 dredge and fill permits and issue water quality certification decisions.

DEQ has reviewed the Joint Application for Permits (received October 28, 2019), City of Burley Bank Barbs Proposal Photos (received October 28, 2019), and Idaho Department of Lands L-45-S-0083 Notice of Application (received October 17, 2019). Based upon its review and consideration of the information listed above, DEQ certifies that if the permittee(s) comply with the terms and conditions imposed by the above-referenced permit, along with the conditions set forth in this water quality certification, then there is reasonable assurance the activity will comply with the applicable requirements of Sections 301, 302, 303, 306, and 307 of the Clean Water Act, the Idaho Water Quality Standards (WQS) (IDAPA 58.01.02), and other appropriate water quality requirements of state law.

This certification does not constitute authorization of the permitted activities by any other state or federal agency or private person or entity. This certification does not excuse the permit holder from the obligation to obtain any other necessary approvals, authorizations, or permits.

Project Description

The proposed project will place up to three rock stream barbs extending a total of approximately 48 feet into the reservoir from the ordinary high water mark; and to include additional shoreline stabilization using rock riprap where needed along portions of approximately 662 linear feet of shoreline. The work is proposed to be completed in the dry when Milner Reservoir water levels are below the work area and working from the top of the bank with a maximum volume of rock to be placed below the OHWM of approximately 892 cubic yards and excavating 834 cubic yards to be deposited in an upland area away from the Snake River.

Antidegradation Review

The WQS contain an antidegradation policy providing three levels of protection to water bodies in Idaho (IDAPA 58.01.02.051).

- Tier I Protection. The first level of protection applies to all water bodies subject to Clean Water Act jurisdiction and ensures that existing uses of a water body and the level of water quality necessary to protect those existing uses will be maintained and protected (IDAPA 58.01.02.051.01; 58.01.02.052.01). Additionally, a Tier I review is performed for all new or reissued permits or licenses (IDAPA 58.01.02.052.07).
- Tier II Protection. The second level of protection applies to those water bodies considered high quality and ensures that no lowering of water quality will be allowed unless deemed necessary to accommodate important economic or social development (IDAPA 58.01.02.051.02; 58.01.02.052.08).
- Tier III Protection. The third level of protection applies to water bodies that have been designated outstanding resource waters and requires that activities not cause a lowering of water quality (IDAPA 58.01.02.051.03; 58.01.02.052.09).

DEQ is employing a water body by water body approach to implementing Idaho's antidegradation policy. This approach means that any water body fully supporting its beneficial uses will be considered high quality (IDAPA 58.01.02.052.05.a). Any water body not fully supporting its beneficial uses will be provided Tier I protection for that use, unless specific circumstances warranting Tier II protection are met (IDAPA 58.01.02.052.05.c). The most recent federally approved Integrated Report and supporting data are used to determine support status and the tier of protection (IDAPA 58.01.02.052.05).

Pollutants of Concern

The primary pollutant of concern for this project is sediment due to inputs from streambank erosion in an urban location. No agricultural lands or rangelands are associated with the project site. As part of the Section 401 water quality certification, DEQ is requiring the applicant comply with various conditions to protect water quality and to meet Idaho WQS, including the water quality criteria applicable to sediment.

Receiving Water Body Level of Protection

This project is located on the Snake River in the Milner Reservoir within the Lake Walcott Subbasin assessment unit (AU) ID17040209SK001_07 (Snake river – Heyburn/Burley Bridge to Milner Dam). This AU has been designated for warm water aquatic life and primary contact recreation. In addition to these uses, all waters of the state are protected for agricultural and industrial water supply, wildlife habitat, and aesthetics (IDAPA 58.01.02.100).

According to DEQ's 2016 Integrated Report, this AU is not fully supporting one or more of its assessed uses. The aquatic life use is not fully supported. Causes of impairment include excess nutrients (total phosphorus). As such, DEQ will provide Tier I protection (IDAPA 58.01.02.051.01) for the aquatic life use.

The contact recreation beneficial use is unassessed. DEQ must provide an appropriate level of protection for the contact recreation use using information available at this time (IDAPA 58.01.02.052.05.b). DEQ reviewed the 2012 Lake Walcott TMDL and determined that the *E. coli* data collected as a geometric mean was well under the water quality standard. Thus, *E. coli* is not impairing the contact recreation beneficial use and DEQ will provide Tier II protection (IDAPA 58.01.02.051.02) in addition to Tier I. The only pollutant of concern associated with this project is sediment. However, sediment is not relevant to recreational uses since sediment will not degrade water quality necessary to support recreational uses, it is therefore unnecessary for DEQ to conduct a Tier II antidegradation analysis.

Protection and Maintenance of Existing Uses (Tier I Protection)

A Tier I review is performed for all new or reissued permits or licenses, applies to all waters subject to the jurisdiction of the Clean Water Act, and requires demonstration that existing uses and the level of water quality necessary to protect existing uses shall be maintained and protected. The numeric and narrative criteria in the WQS are set at levels that ensure protection of existing and designated beneficial uses.

Water bodies not supporting existing or designated beneficial uses must be identified as water quality limited, and a total maximum daily load (TMDL) must be prepared for those pollutants causing impairment. Once a TMDL is developed, discharges of causative pollutants shall be consistent with the allocations in the TMDL (IDAPA 58.01.02.055.05). Prior to the development of the TMDL, the WQS require the application of the antidegradation policy and implementation provisions to maintain and protect uses (IDAPA 58.01.02.055.04).

During the construction phase, the applicant will implement, install, maintain, monitor, and adaptively manage best management practices (BMPs) directed toward reducing erosion and minimizing turbidity levels in receiving water bodies downstream of the project. In addition, permanent erosion and sediment controls will be implemented, which will minimize or prevent future sediment contributions from the project area. As long as the project is conducted in accordance with the provisions of the project plans, Section 404 permit, and conditions of this certification, then there is reasonable assurance the project will comply with the state's numeric and narrative criteria. These criteria are set at levels that protect and maintain designated and existing beneficial uses. In addition, the project will be consistent with the *Lake Walcott Subbasin Assessment and Total Maximum Daily Loads – Five-Year Reviews* (DEQ 2012). The proposed project will comply with the TMDL based on the following best management practices:

1. The project activity will occur during the Milner Reservoir drawdown, thus allowing the activity to occur in the dry.
2. All excavated material will be hauled off-site in an upland area so it does not reenter the Snake River.
3. An excavator will be used to work from the top of the streambank. No equipment will be allowed to work below the ordinary high water mark of the Snake River.
4. The rock riprap will be washed with water and clear of fine materials, prior to installation.
5. Rock riprap placement will occur only in the excavated areas and will immediately be compacted using an excavator.

6. A silt fence or an 18” coir log will be installed at the edge of the excavation to keep any sediment from leaving the work area.

There is no available information indicating the presence of any existing beneficial uses aside from those that are already designated and discussed above; therefore, the permit ensures that the level of water quality necessary to protect both existing and designated uses is maintained and protected in compliance with the Tier I provisions of Idaho’s WQS (IDAPA 58.01.02.051.01 and 58.01.02.052.07).

Conditions Necessary to Ensure Compliance with Water Quality Standards or Other Appropriate Water Quality Requirements of State Law

General Conditions

1. This certification is conditioned upon the requirement that any modification (e.g., change in BMPs, work windows, etc.) of the permitted activity shall first be provided to DEQ for review to determine compliance with Idaho WQS and to provide additional certification pursuant to Section 401. Such modifications may not be implemented until DEQ has determined whether additional certification is necessary.
2. DEQ reserves the right to modify, amend, or revoke this certification if DEQ determines that, due to changes in relevant circumstances—including without limitation, changes in project activities, the characteristics of the receiving water bodies, or state WQS—there is no longer reasonable assurance of compliance with WQS or other appropriate requirements of state law.
3. If ownership of the project changes, the certification holder shall notify DEQ, in writing, upon transferring this ownership or responsibility for compliance with these conditions to another person or party. The new owner/operator shall request, in writing, the transfer of this water quality certification to his/her name.
4. A copy of this certification must be kept on the job site and readily available for review by any contractor working on the project and any federal, state, or local government personnel.
5. Project areas shall be clearly identified in the field prior to initiating land-disturbing activities to ensure avoidance of impacts to waters of the state beyond project footprints.
6. The applicant shall provide access to the project site and all mitigation sites upon request by DEQ personnel for site inspections, monitoring, and/or to ensure that conditions of this certification are being met.
7. The applicant is responsible for all work done by contractors and must ensure the contractors are informed of and follow all the conditions described in this certification and the Section 404 permit.
8. If this project disturbs more than 1 acre and there is potential for discharge of stormwater to waters of the state, coverage under the EPA Stormwater Construction General Permit *must* be obtained. More information can be found at <https://www.epa.gov/npdes-permits/stormwater-discharges-construction-activities-region-10>.

Fill Material

1. Fill material subject to suspension shall be free of easily suspended fine material. The fill material to be placed shall be clean material only.
2. Fill material shall not be placed in a location or in a manner that impairs surface or subsurface water flow into or out of any wetland area.
3. Placement of fill material in existing vegetated wetlands shall be minimized to the greatest extent possible.
4. All temporary fills shall be removed in their entirety on or before construction completion.
5. Excavated or staged fill material must be placed so it is isolated from the water edge or wetlands and not placed where it could re-enter waters of the state uncontrolled.

Erosion and Sediment Control

1. BMPs for sediment and erosion control suitable to prevent exceedances of state WQS shall be selected and installed before starting construction at the site. One resource that may be used in evaluating appropriate BMPs is DEQ's *Catalog of Stormwater Best Management Practices for Idaho Cities and Counties*, available online at <http://www.deq.idaho.gov/media/494058-entire.pdf>. Other resources may also be used for selecting appropriate BMPs.
2. One of the first construction activities shall be placing permanent and/or temporary erosion and sediment control measures around the perimeter of the project or initial work areas to protect the project water resources.
3. Permanent erosion and sediment control measures shall be installed in a manner that will provide long-term sediment and erosion control to prevent excess sediment from entering waters of the state.
4. Permanent erosion and sediment control measures shall be installed at the earliest practicable time consistent with good construction practices and shall be maintained as necessary throughout project operation.
5. Top elevations of bank stabilization shall be such that adequate freeboard is provided to protect from erosion at 100-year design flood elevation.
6. Structural fill or bank protection shall consist of materials that are placed and maintained to withstand predictable high flows in the waters of the state.
7. A BMP inspection and maintenance plan must be developed and implemented. At a minimum, BMPs must be inspected and maintained daily during project implementation.
8. BMP effectiveness shall be monitored during project implementation. BMPs shall be replaced or augmented if they are not effective.
9. All construction debris shall be properly disposed of so it cannot enter waters of the state or cause water quality degradation.
10. Disturbed areas suitable for vegetation shall be seeded or revegetated to prevent subsequent soil erosion.
11. Maximum fill slopes shall be such that material is structurally stable once placed and does not slough into the stream channel during construction, during periods prior to revegetation, or after vegetation is established.

12. To the extent reasonable and cost-effective, the activity submitted for certification shall be designed to minimize subsequent maintenance.
13. Sediment from disturbed areas or able to be tracked by vehicles onto pavement must not be allowed to leave the site in amounts that would reasonably be expected to enter waters of the state. Placement of clean aggregate at all construction entrances or exits and other BMPs such as truck or wheel washes, if needed, must be used when earth-moving equipment will be leaving the site and traveling on paved surfaces.

In-water Work

1. Work in open water is to be kept at a minimum and only when necessary. Equipment shall work from an upland site to minimize disturbance of waters of the state. If this is not practicable, appropriate measures must be taken to ensure disturbance to the waters of the state is minimized.
2. Construction affecting the bed or banks shall take place only during periods of low flow.
3. Fording of the channel is not permitted. Temporary bridges or other structures shall be built if crossings are necessary.
 - a. Temporary crossings must be perpendicular to channels and located in areas with the least impact. The temporary crossings must be supplemented with clean gravel or treated with other mitigation methods at least as effective in reducing impacts. Temporary crossings must be removed as soon as possible after the project is completed or the crossing is no longer needed.
4. Heavy equipment working in wetlands shall be placed on mats or suitably designed pads to prevent damage to the wetlands.
5. Activities in spawning areas must be avoided to the maximum extent practicable.
6. Work in waters of the state shall be restricted to areas specified in the application.
7. Measures shall be taken to prevent wet concrete from entering into waters of the state when placed in forms and/or from truck washing.
8. Activities that include constructing and maintaining intake structures must include adequate fish screening devices to prevent fish entrainment or capture.
9. Stranded fish found in dewatered segments should be moved to a location (preferably downstream) with water.
10. To minimize sediment transport, stream channel or stream bank stabilization must be completed prior to returning water to a dewatered segment.

Pollutants/Toxics

1. The use of chemicals such as soil stabilizers, dust palliatives, sterilants, growth inhibitors, fertilizers, and deicing salts during construction and operation should be limited to the best estimate of optimum application rates. All reasonable measures shall be taken to avoid excess application and introduction of chemicals into waters of the state.

Vegetation Protection and Restoration

1. Disturbance of existing wetlands and native vegetation shall be kept to a minimum.

2. To the maximum extent practical, staging areas and access points should be placed in open, upland areas.
3. Fencing and other barriers should be used to mark the construction areas.
4. Where possible, alternative equipment should be used (e.g., spider hoe or crane).
5. If authorized work results in unavoidable vegetative disturbance, riparian and wetland vegetation shall be successfully reestablished to function for water quality benefit at pre-project levels or improved at the completion of authorized work.

Dredge Material Management

1. Upland disposal of dredged material must be done in a manner that prevents the material from re-entering waters of the state.

Management of Hazardous or Deleterious Materials

1. Petroleum products and hazardous, toxic, and/or deleterious materials shall not be stored, disposed of, or accumulated adjacent to or in the immediate vicinity of waters of the state. Adequate measures and controls must be in place to ensure that those materials will not enter waters of the state as a result of high water, precipitation runoff, wind, storage facility failure, accidents in operation, or unauthorized third-party activities.
2. Vegetable-based hydraulic fluid should be used on equipment operating in or directly adjacent to the channel if this fluid is available.
3. Daily inspections of all fluid systems on equipment to be used in or near waters of the state shall be done to ensure no leaks or potential leaks exist prior to equipment use. A log book of these inspections shall be kept on site and provided to DEQ upon request.
4. Equipment and machinery must be removed from the vicinity of the waters of the state prior to refueling, repair, and/or maintenance.
5. Equipment and machinery shall be steam cleaned of oils and grease in an upland location or staging area with appropriate wastewater controls and treatment prior to entering a water of the state. Any wastewater or wash water must not be allowed to enter a water of the state.
6. Emergency spill procedures shall be in place and may include a spill response kit (e.g., oil absorbent booms or other equipment).
7. In accordance with IDAPA 58.01.02.850, in the event of an unauthorized release of hazardous material to state waters or to land such that there is a likelihood that it will enter state waters, the responsible persons in charge must:
 - a. Make every reasonable effort to abate and stop a continuing spill.
 - b. Make every reasonable effort to contain spilled material in such a manner that it will not reach surface or ground waters of the state.
 - c. Call 911 if immediate assistance is required to control, contain, or clean up the spill. If no assistance is needed in cleaning up the spill, contact the appropriate DEQ regional office during normal working hours or Idaho State Communications Center after normal working hours (1-800-632-8000). If the spilled volume is above federal reportable quantities, contact the National Response Center (1-800-424-8802). The Twin Falls Regional Office may be contacted at: 208-736-2190 / 800-270-1663.

- d. Collect, remove, and dispose of the spilled material in a manner approved by DEQ.


Required Notification

The permittee must notify the Twin Falls Regional Office when authorized *work begins* and when the authorized *work ends*. Please contact Balthasar B. Buhidar, Ph.D. at (208) 736-2190 or by email at Balthasar.buhidar@deq.idaho.gov.

Right to Appeal Final Certification

The final Section 401 Water Quality Certification may be appealed by submitting a petition to initiate a contested case, pursuant to Idaho Code § 39-107(5) and the “Rules of Administrative Procedure before the Board of Environmental Quality” (IDAPA 58.01.23), within 35 days of the date of the final certification.

Questions or comments regarding the actions taken in this certification should be directed to Balthasar B. Buhidar, Ph.D., Twin Falls Regional Office, (208) 736-2190, or at Balthasar.buhidar@deq.idaho.gov.



Sue Switzer
Regional Administrator
Twin Falls Regional Office