

**MODIFICATION OF REUSE PERMIT
APPENDIX C TO PERMIT I-008-05**

Permittee Name: J.R. Simplot Company

Effective Date of this Modification: November 22, 2016

Description of Modification

The purpose of this Permit Modification is to extend the due date to complete seepage testing on the Effluent Storage Pond. The permit set a due date at ten (10) years after the previous test. The permittee has requested that the due date be extended until the next time the plant will be shut down in order to provide the most suitable conditions to perform the seepage test.

Modification

Section 3. Compliance Schedule for Required Activities shall be replaced with the following, which extends the due date for seepage testing the Effluent Storage Pond by nine (9) months.

Compliance Activity (CA) Number and Completion Due Date	Compliance Activity Description										
CA-008-05 As Specified	<p>Seepage Testing: The following table shows the date by which the permittee shall complete seepage testing on the specified lagoons:</p> <table border="1" style="width: 100%;"> <thead> <tr> <th style="text-align: left;">Lagoon:</th> <th style="text-align: left;">Seepage Test Due Date:</th> </tr> </thead> <tbody> <tr> <td>Evaporation Lagoon 1, 2 and 3 (individually or combined)</td> <td>Prior to Use</td> </tr> <tr> <td>Emergency Storage Lagoon 1 and 2 (individually or combined)</td> <td>Prior to Use</td> </tr> <tr> <td>Effluent Storage Pond</td> <td>April, 2017</td> </tr> <tr> <td>Silt Water Pond</td> <td>No requirement this permit term. Last tested in July, 2011</td> </tr> </tbody> </table> <p>Submit to DEQ for review and approval a proposed schedule and procedure for performing the required seepage tests at least 42 days prior to the planned seepage test. Seepage test procedures are available at: http://www.deq.idaho.gov/water-quality/wastewater/lagoon-seepage-testing.aspx <u>The seepage test procedures shall be sealed by the Idaho licensed professional engineer or professional geologist in responsible charge for the test.</u></p> <p>Seepage tests shall be completed in accordance with the procedures approved by DEQ. The seepage test report shall be sealed by the person in responsible charge and submitted within 90 days after completion of the seepage test.</p> <p>The lagoons shall not be put into service until seepage test results show a seepage rate of 0.125 in/day or less.</p>	Lagoon:	Seepage Test Due Date:	Evaporation Lagoon 1, 2 and 3 (individually or combined)	Prior to Use	Emergency Storage Lagoon 1 and 2 (individually or combined)	Prior to Use	Effluent Storage Pond	April, 2017	Silt Water Pond	No requirement this permit term. Last tested in July, 2011
Lagoon:	Seepage Test Due Date:										
Evaporation Lagoon 1, 2 and 3 (individually or combined)	Prior to Use										
Emergency Storage Lagoon 1 and 2 (individually or combined)	Prior to Use										
Effluent Storage Pond	April, 2017										
Silt Water Pond	No requirement this permit term. Last tested in July, 2011										

This modification described herein and referred to as Appendix C is hereby approved. This appendix to the permit is incorporated into, and constitutes a part of, Reuse Permit I-008-05. This appendix must be attached to the permit. The permit is incomplete and unlawful under IDAPA 58.01.17 *Recycled Water Rules* without this appendix attached.

Signed,



Aaron Scheff
Regional Administrator
Idaho Department of Environmental Quality
Boise Regional Office

Date: 11/22/2016